

Project No.  
**9769.000.000**

October 2, 2017

Mr. Mike O'Hara  
North Waterfront Cove, LLC  
c/o Tim Lewis Communities  
3300 Douglas Boulevard, Suite 450  
Roseville, CA 95661

Subject: Encinal Terminals  
Alameda, California

## **SLOPE STABILITY ANALYSIS WITH GROUND IMPROVEMENT**

Dear Mr. O'Hara:

We prepared this supplemental evaluation of the shoreline seismic slope stability of the Encinal Terminals property in Alameda, California. We performed the analyses summarized in this letter in order to further evaluate shoreline stability and refine the ground improvement concept for planning purposes. This evaluation is intended to supplement our geotechnical report for the planned site development. As discussed in that report, we identified a potential for excessive shoreline displacement during a design-level earthquake.

## **GEOMETRY AND IDEALIZED SOIL PROFILES**

Along the western shoreline, under the existing wharf, four cross sections were prepared; three cross sections are perpendicular to the wharf, and one is longitudinal to the wharf. Additionally, two sections were prepared on the northern shoreline, and two were prepared on the eastern shoreline. Figure 2 depicts the locations of the sections, and Figure 5 shows the sections. The slope of the mud line in these cross sections was determined using plans depicting the dredging of the area prior to the construction of the C2 wharf structure in the 1960s. In all of these cross sections, the mud line was determined based on 2013 bathymetry provided to us by Carlson, Barbee and Gibson (CBG), the project Civil Engineer.

The subsurface exploration and geotechnical conditions are presented in the geotechnical exploration report (ENGEO, 2017). Figure 2 presents the mapped historic shoreline. The strength profile of the subsurface soils are deemed to be different on each side of the historic shoreline, particularly where dredging would have occurred.

## **SEISMIC DESIGN CRITERIA**

Based on the site geology and type of structure being analyzed, it is our opinion that the seismic performance of the shoreline and the effects on the existing wharf, and planned structures, due to slope movement, be designed for the Design Earthquake (DE) (defined as  $2/3$  of the  $MCE_R$ ). To develop the site DE, a site-specific site response analysis was performed.

Since the depth of the bedrock at the site is over 500 feet, the base of the site response was evaluated at the interface for a Site Class D stiff soil site. This seismic hazard was evaluated by performing a site-specific hazard analysis.

The site-specific spectral response for a Site Class D, was evaluated in accordance with the methodologies described in Chapter 21 of ASCE 7-10. The following approach was used to develop a site-specific DE spectra for a Site Class D:

- A probabilistic seismic hazard analysis (PSHA) to develop a risk-targeted maximum rotated response spectrum corresponding to a 2-percent probability of exceedance in 50 years (2,500-year return period).
- A site-specific deterministic analysis (DSHA) to develop 84th-percentile maximum rotated geometric mean response spectrum considering a moment magnitude 7.3 earthquake occurring on the Hayward fault a moment magnitude 8.1 earthquake occurring on San Andreas fault.
- Comparison of the DSHA and the Deterministic Lower Limit in accordance with Section 21.2.2 of ASCE 7-10.
- Comparison of the PSHA and the DSHA spectra to obtain the site-specific  $MCE_R$  ground motions for the site.
- Development of DE response spectrum as  $2/3$  of  $MCE_R$  and comparison with 80 percent of the response spectrum determined in accordance with Section 11.4.7 of ASCE 7-10.

## Probabilistic Seismic Hazard Analysis

### Probabilistic Model

EZFRISK (Risk Engineering, 2015) was used to develop a probabilistic seismic hazard analysis (PSHA) for the project site for a return period of 2,500 years. EZFRISK calculates seismic hazard using the standard methodology for hazard analysis. The seismic-hazard calculations can be represented by the following equation, which is an application of the total-probability theorem.

$$H(a) = \sum_i v_i \iint P[A > a|m, r] f_{Mi}(m) f_{Ri|Mi}(r, m) dr dm$$

In this equation, the hazard  $H(a)$  is the annual frequency of earthquakes that produce a ground motion amplitude  $A$  higher than the selected amplitude  $a$ . Amplitude  $A$  may represent peak ground acceleration, velocity or displacement, or it may represent spectral pseudo-acceleration for a given frequency. The summation in the equation shown extends over all sources, i.e. over all faults and areas,  $v_i$  is the annual rate of earthquakes (with magnitude higher than some threshold  $M_i$ ) in source  $i$ , and  $f_{Mi}(m)$  and  $f_{Ri|Mi}(r, m)$  are the probability density functions on magnitude and distance, respectively.  $P[A > a|m, r]$  is the probability that an earthquake of magnitude  $m$  at distance  $r$  produces a ground-motion amplitude  $A$  at the site that is greater than  $a$ .

Seismic sources may be either faults or area sources; the specification of source geometries and the calculation of  $fR_i/M_i$ , are performed differently for these two types of sources.

### Fault Database and Model

The USGS 2008 National Seismic Hazard Map was selected as the seismic model. The following table, extracted from EZFRISK, shows the seismic sources used in the PSHA analysis:

**TABLE 1: Seismic Sources**

SOURCE	CLOSEST DISTANCE (km)	MOMENT MAGNITUDE ( $M_w$ )	FAULT MECHANISM	SITE LIES
Bartlett Springs	130	7.3	Strike Slip	S
Calaveras	22.38	7.025	Strike Slip	W
California Gridded	0.00	7	SS R	Above
California Gridded Deep	36.08	7.2	Intraslab	S
Collayomi	116.96	6.7	Strike Slip	S
Great Valley 1	167.48	6.8	Reverse	S
Great Valley 10	168.58	6.501	Reverse	NW
Great Valley 11	190.49	6.6	Reverse	NW
Great Valley 2	145.68	6.501	Reverse	S
Great Valley 3, Mysterious Ridge	96.9	7.1	Reverse	S
Great Valley 4a, Trout Creek	79.48	6.6	Reverse	S
Great Valley 4b, Gordon Valley	54.65	6.8	Reverse	S
Great Valley 5, Pittsburg Kirby Hills	45.94	6.7	Strike Slip	SW
Great Valley 7	59.92	6.9	Reverse	W
Great Valley 8	98.01	6.8	Reverse	NW
Great Valley 9	132.06	6.8	Reverse	NW
Green Valley Connected	27.44	6.8	Strike Slip	SW
Greenville Connected	39.19	7	Strike Slip	W
Greenville Connected U	39.19	7	Strike Slip	W
Hayward-Rodgers Creek	6.46	7.334	Strike Slip	SW
Hosgri	187.29	7.3	Strike Slip	N
Hunting Creek-Berryessa	74.99	7.1	Strike Slip	S
Maacama-Garberville	96.21	7.4	Strike Slip	SE
Monte Vista-Shannon	38.07	6.501	Reverse	N
Monterey Bay-Tularcitos	96.2	7.3	Strike Slip	N
Mount Diablo Thrust	23.57	6.7	Reverse	SW
Northern San Andreas	22.69	8.05	Strike Slip	NE
Ortogonalita	103.19	7.1	Strike Slip	NW
Point Reyes	53.56	6.9	Reverse	E
Quien Sabe	123.56	6.6	Strike Slip	NW
Rinconada	130.59	7.5	Strike Slip	N
SAF - creeping segment	128.25	6.7	Strike Slip	NW
San Andreas Creeping Section Gridded	90.27	6	Strike Slip	NW
San Gregorio Connected	29.89	7.5	Strike Slip	E

SOURCE	CLOSEST DISTANCE (km)	MOMENT MAGNITUDE ( $M_w$ )	FAULT MECHANISM	SITE LIES
Shear 1 Gridded	133.43	7.6	Strike Slip	SW
West Napa	42.74	6.7	Strike Slip	S
Zayante-Vergeles	80.87	7	Strike Slip	N

A total of four attenuation equations from the Next Generation Attenuation West 2 (NGA West 2) project were used. These include Abrahamson et al. (2014), Boore et al. (2014), Campbell and Bozorgnia (2014), and Chiou and Youngs (2014). All four empirical attenuation equations were for a spectral damping of 5 percent and were assigned equal weights (0.25) in the analyses.


### Deterministic Analysis

The deterministic analysis involves developing the 84th percentile geometric mean response spectrum for a spectral damping of 5 percent of critical damping using the sources in Table 1 and the aforementioned attenuation equations (NGA West 2). The gridded seismic sources were not included in the deterministic evaluation. Based on the analysis, the deterministic ground motions are governed by a magnitude 7.3 earthquake on the Hayward fault with a closest distance to the site of approximately 6.5 km.

### Resulting Base Spectra

The geometric mean values from EZFRISK were obtained and the maximum rotated factors were applied based on Shahi and Baker (2014). For PSHA, risk factors were also applied based on map values. Per ASCE 7-10,  $MCE_R$  is controlled by the lesser of the PSHA and 84th percentile of the DSHA. Exhibit 1 and Table 2 depict the recommended Site Class D  $MCE_R$  and DE response spectrum. The same exhibits show the DE response spectrum, which is 2/3 of the  $MCE_R$ . The DE level was then compared to 80 percent of the mapped spectrum and the maximum values were selected.

### **EXHIBIT 1: Site-Specific Response Spectra at the Base**



**TABLE 2: Site-Specific Base Response Spectra (Site Class D – Stiff Soil)**

PERIOD (SECONDS)	RECOMMENDED SPECTRAL ACCELERATION (G)	
	RISK TARGETED – MAXIMUM ROTATED MCE <sub>R</sub>	MAXIMUM ROTATED DE
0.01	0.87	0.579
0.02	0.88	0.588
0.100	1.48	0.987
0.118	1.59	1.062
0.120	1.61	1.070
0.20	1.96	1.306
0.30	2.11	1.407
0.40	2.08	1.389
0.500	1.93	1.289
0.589	1.75	1.169
0.60	1.73	1.156
0.70	1.58	1.056
0.80	1.45	0.964
1.00	1.21	0.807
2.00	0.57	0.379
3.00	0.37	0.244
4.00	0.26	0.174
5.00	0.20	0.132
6.00	0.15	0.100
7.00	0.13	0.086
8.00	0.11	0.075

#### Horizontal Ground Motion Selection and Matching

Seven pairs of recorded ground motions were selected as seed motions. The motions were then matched to the recommended DE response spectrum shown on Exhibit 1. In developing the input stiff soil motions for our site-response analysis, time histories that reflect the potential ground motions at the site were selected. The NEHRP report titled “Selecting and Scaling Earthquake Ground Motions for Performing Response-History Analysis”, dated November of 2011, suggests that the most important factors affecting an analysis using recorded ground motions, is the spectral shape, and the existence of a velocity pulse. In addition, the effective duration, magnitudes and peak ground acceleration are also of importance. Another factor affecting earthquake records is fault type. It is of note that the main rupture mode of the Hayward Fault is a strike slip, but oblique faulting from the main trace of the Hayward fault is also possible. As an example, the 1989 Loma Prieta earthquake was on a reverse-oblique fault off the San Andreas main trace. By selecting four motions that represent a strike-slip fault, and three that represent reverse/normal faulting, the ranges of potential faulting events at the site have been encapsulated.

Due to proximity of the site to active faults, three of the seven seed motions were selected to have a velocity pulse. In identifying pulse-like motions, the PEER Ground Motion Database was used, which uses the procedure developed by Shahi and Baker (2010). The pulse characteristics were retained after the matching process had been completed.

The selected ground motions are listed in Table 3. The initial and matched 5 percent response spectra of the selected ground motions are shown in Appendix A.

**TABLE 3: Selected Ground Motions for Horizontal Spectral Matching**

NO.	EARTHQUAKE	NGA #	PULSE PERIOD (sec)	MAG. (M <sub>w</sub> )	R <sub>rup</sub> (km)	FAULT TYPE	V <sub>s30</sub> (m/sec)	D <sub>5-95</sub> (sec)	PGA (g)
1	Imperial Valley-06	164	-	6.53	15.2	strike slip	472	36.4	0.23
2	Landers	850	-	7.28	21.8	strike slip	359	31.7	0.23
3	Northridge-01	1004	0.93	6.69	8.44	Reverse	380	8.50	1.20
4	Chi-Chi, Taiwan	1495	-	7.62	6.34	Reverse Oblique	359	26.8	0.32
5	Duzce, Turkey	1602	0.88	7.14	12.0	strike slip	294	9.00	1.11
6	Iwate, Japan	5780	-	6.90	20.8	Reverse	346	15.1	0.45
7	Darfield, New Zealand	6911	9.92	7.00	7.29	strike slip	326	9.50	0.66

### Seismic Site-Response Analysis


Site response analysis were performed for three areas of the site as a function of the thickness of the soft soils, specifically the thickness of Young Bay Mud (Exhibit 4). One-dimensional (1-D), site-specific site response analysis using the computer program DEEPSOIL (Hashash et al., 2016) was performed.

### One-Dimensional Site Response


The 1-D equivalent linear site response analyses were performed to develop seismic demand for the wharf's inertial response. Based on the collected data in the previous explorations, shear wave velocity profiles were developed for use in the 1-D soil column. The shear strain modulus reduction and damping functions were developed in accordance with Darendeli (2001), and by using the laboratory results from the publicly available data from the design of the new eastern span of the Bay Bridge.

Exhibit 3 (a, b and c) presents the average non-linear response spectra for the three zones (Exhibit 4) at the wharf locations. The spectra are compared to the 80-percent cap of the design mapped spectra based on ASCE 7-10. The recommended DE spectra is the envelope of the 80-percent cap and the site-response.

**EXHIBIT 3: Summary of DE Response Spectra (a)**




**EXHIBIT 3: Summary of DE Response Spectra (b)**






**EXHIBIT 3: Summary of DE Response Spectra (c)**



**EXHIBIT 4: Schematic Showing Areas of Site Response**





## SLOPE STABILITY ANALYSIS – LIMIT EQUILIBRIUM

A simplified deformation analysis was performed using the computer program SLIDE (Version 6) to evaluate seismic stability using “pseudostatic” methods, and potential seismic deformation was estimated using simplified displacement analyses to index stability of the perimeter of the site. SLIDE is a limit equilibrium program that allows the user various search routines to locate the minimum factor of safety and critical slip surface. For our analysis, Spencer’s Method (Spencer, 1967) was used. Circular searching methods were used to analyze the existing conditions. In performing our analyses, a groundwater level of approximately 9 feet below existing ground surface, water level in the Alaska Basin at approximately Mean Sea Level, a peak ground acceleration (PGA) of 0.33g per the results of our DE site-specific ground response analysis, and a moment magnitude ( $M_w$ ) of 7.3 were used.

A “pseudostatic” screening analysis was used as recommended in the California Geological Survey’s (CGS) SP117A “Guidelines for Evaluating and Mitigating Seismic Hazards in California”. To estimate displacement, the procedures in the publication “Seismic Analysis and Design of Retaining Walls, Buried Slopes, and Embankments,” by the National Cooperative Highway Research Program Report 611 (NCHRP, 2008) were used. Specifically, a wave scattering coefficient of 0.9 per Figure 6-13 in NCHRP 611 was used. In addition, a reduction of the resulting  $k_{max}$  of 50 percent per the commentary in section 8.3.1 of the NCHRP report was applied. The resulting  $k_h$  for the pseudostatic checks was approximately 0.15g; due to limitations of this method, actual deformations will be on the order of 2 to 6 inches, approximately.

Along the western and northern portions of the site (Sections 1 through 6), the slopes did not pass this check and deformations into the proposed building areas are anticipated to be over 1 foot without mitigation. Along the eastern side of the site (Sections 7 and 8), the proposed buildings are set back approximately 50 to 100 feet from the shoreline. The area between the shoreline and the building area is occupied by parking and drive areas related to the adjacent Fortman Marina; this roadway and parking are off the developable property and are owned by others. Section 8 was selected as the most critical condition along the eastern shoreline, due to the thickness of the Young Bay Mud. Analysis of Section 8 is attached in Appendix B.

Prior to performing slope stability analyses, the shear strength of the soil profile was evaluated. To obtain shear strength data, in-situ Standard Penetration Tests (SPTs), in-situ Cone Penetrometer Tests (CPTs), Unconsolidated Undrained Triaxial Compression Tests, Laboratory Miniature Vane Shear Tests and laboratory index tests were performed. The lab strength and in-situ data were compared with empirical correlations of SPT blow counts, plasticity index (PI) and soil type. Based on the data review, idealized soil profiles were developed. The following table summarizes the strength parameters used for each soil layer:

**TABLE 4**

SOIL LAYER	UNIT WEIGHT	COHESION (PSF)	FRICTION ANGLE (DEG)	NOTES
Fill	120	0	38	
Young Bay Mud (crust inland)	110	600	0	Overconsolidated due to marsh and past site use
Young Bay Mud (inland)	100	420 + 10 psf/foot	0	Overconsolidated due to past site use and minor surcharging when converted to storage for shipping containers

SOIL LAYER	UNIT WEIGHT	COHESION (PSF)	FRICTION ANGLE (DEG)	NOTES
Young Bay Mud *	90	100 + 10 psf/foot	0	
Old Bay Clay	110	2000	0	

## WESTERN AND NORTHERN SHORELINE DEEP SOIL MIXING

Initial analyses of the cross sections along the western and northern shorelines indicate that excessive seismic deformations could occur in the existing condition. A Deep Soil Mix (DSM) buttress was added to our slope stability models to mitigate movement in these areas. To analyze the effectiveness of a DSM buttress in reducing potential displacement to acceptable ranges, pseudostatic analyses of a buttress extending to the bottom of the Young Bay Mud layer with a width to height ratio of  $\frac{3}{4}$ :1, were performed. The DSM would consist of below-ground shear walls created by overlapping columns of in-situ soil mixed with water and cement. The resulting shear walls would be oriented perpendicular to the shoreline. The shear strength of the mixed soil would be approximately 100 psi; this would result in an average shear strength of the mixed zone of approximately 5,000 psf (assuming 30-percent replacement ratio).

To analyze the stability of the buttress concept, a block search for failure surfaces that pass underneath and through the DSM buttress, were performed. Additionally, circular surfaces passing under the buttress were searched. The results of the analysis of one of the northern cross-section (Section 5) was used to confirm the general approach. This cross section was selected due to the presence of relatively thick Young Bay Mud. Attached in Appendix B is the output of these analyses showing the critical surfaces from each search of Section 5. The results of these analyses indicate that seismic displacements behind and through the DSM should be less than 6 inches.

The design of the DSM buttress will still need to be refined with additional analysis to confirm final dimensions and layout based on type of equipment proposed by the contractor that will perform the work. The criteria should consider similar displacements to those discussed in this section as well as internal and external stability checks. ENGEO should be retained to work with the contractor to refine and optimize the design of the DSM buttress. ENGEO should be retained to review the deep soil mixing contractor submittals.

The DSM buttress should be integrated with the land plan. Due to differential site response movement of the DSM buttresses and the unimproved soil, it is recommended that any building on a shallow foundation be entirely supported on or off the DSM zone. If this is infeasible due to land planning constraints, then the interaction between the buildings, the DSM buttress and the unimproved soil should be further analyzed. Buildings that straddle the DSM zone and unimproved soil behind will likely need to be supported of deep foundations.

## Non-Linear Plaxis Analysis


The design team selected to evaluate the slope movement below the wharf in more detail to refine the estimated kinematic loading on the structure. The two-dimensional (2D) Finite Element Model (FEM) dynamic analysis was used to refine the strain-stress behavior and potential kinematic loads at the wharf piled-foundations during ground shaking. As inputs for the 2D non-linear FEM analysis, the outputs from the 1D non-linear site response described previously in this report were used.

Plaxis is a two-dimensional finite element program for geotechnical and other applications developed by Plaxis BV (2012). The analysis input motion is specified at the base of the analysis section (150 to 200 feet below top of wharf), as a “outcropping” ground motion. The “outcropping” ground motions are the same as the 1D DeepSoil analysis described above.


Various constitutive soil models are available in Plaxis. The Mohr-Coulomb model was used for the non-linear seismic deformation analyses. The Mohr-Coulomb model consists of elastic-perfectly-plastic stress-strain relationships. Therefore, the materials are elastic before yielding. To make the elastic portion of the analysis reasonable, the outputs from DeepSoil were used to obtain the strain-compatible modulus and damping values for the shaking conditions. The analysis results from DeepSoil provide the basis for the strain-compatible shear modulus and damping values to be used in the elastic portion of the Mohr-Coulomb model in the Plaxis analyses. The “perfectly-plastic” portion of the Mohr-Coulomb model is specified as the appropriate shear strength of the material as presented on table 4.

Exhibits 5 through 7 show the meshed analyzed sections, and table 5 shows additional soil properties used on the Plaxis analysis.


**EXHIBIT 5: Section 2-2 Mesh**



**EXHIBIT 6: Section 3-3 Mesh**



**EXHIBIT 7: Section 4-4 Mesh**




**TABLE 5: Plaxis Additional Soil Parameters**

MATERIAL MODEL DRAINAGE TYPE	UNITS	FILL MOHR- COULOMB DRAINED	CH-SC MOHR- COULOMB DRAINED	YBM (RANGE OF VALUES) MOHR- COULOMB UNDRAINED (B)	OBC MOHR- COULOMB UNDRAINED (B)
$\gamma_{unsat}$	lbf/ft <sup>3</sup>	115	125	-	120
$\gamma_{sat}$	lbf/ft <sup>3</sup>	115	125	100	120
Rayleigh $\alpha$		0.4189	0.4189	0.1663	0.4189
Rayleigh $\beta$		0.02122	0.02122	8.43E-03	0.02122
E	lbf/ft <sup>2</sup>	3.37E+06	2.19E+07	3.98E+04 - 7.57E+05	1.04E+07
G	lbf/ft <sup>2</sup>	1.25E+06	8.74E+06	1.99E+04 - 2.70E+05	3.73E+06
$c'_{ref}$	lbf/ft <sup>2</sup>	See Table 4	See Table 4	See Table 4	See Table 4
$\phi$ (phi)	°	See Table 4	See Table 4	See Table 4	See Table 4
$V_s$	ft/s	590	1000	80-300	800-900
$K_{0,x}$		0.38	0.44	0.65	0.65
$K_{0,z}$		0.38	0.44	0.65	0.65


Plaxis uses Rayleigh Damping formulations with two-frequency scheme. This results in under-damping between these frequencies and over-damping outside of this range. The frequencies are a function of the earthquake's predominant period and the period of the soil mass. The frequencies used for these analyses were 0.1 Hz and 7.5Hz.

The same ground motions as the 1D analysis were used at the bottom of the 2D models to evaluate average deformations at the foundations of the wharf. Exhibits 8 through 10 show a sample of the deformation distribution at the bottom of wharf for a selected ground motion. Exhibit 11 shows the resulting deformations at the middle of the wharf for each section analyzed. Additional deformation-profiles were provided to the marine structural engineers, to evaluate kinematic loads on the wharf foundations. The averaged deformations for the soils under the wharf within the areas of historical dredging, is shown to be less than 1 foot. The deformations north of the historical shoreline, and where the thickness of the YBM is up to 50 feet, are shown to be in excess of 3 feet. Kinematic loads should be added to inertial loads. Kinematic loading, however, does not occur at the same time or elevation as the inertial loading. Therefore, it is common not to apply 100-percent of both loads when superimposing them. On other similar projects, for example, structural engineers have added a quarter of the inertial load to the kinematic load when superimposing the two conditions.

**EXHIBIT 8: Section 2-2 Horizontal Displacement Landers**




**EXHIBIT 9: Section 3-3 Horizontal Displacement Iwate**






**EXHIBIT 10: Section 4-4 Horizontal Displacement Landers**



**EXHIBIT 11: Section 2-2 Horizontal Displacement At Middle of Pier**




Deformation at Section 3-3 (Middle)

The graph displays lateral deformation (ft) on the x-axis (ranging from -1.4 to 0) against elevation (ft) on the y-axis (ranging from -10 to -30). Eight seismic events are plotted, showing their respective deformation profiles. The curves generally indicate that lateral deformation increases as elevation increases, with the Darfield 320 event showing the most significant deformation at higher elevations.

Legend:

- Northridge 320
- Landers 320
- ImpVI 320
- ChiChi 320
- Duzce 320
- Iwate 320
- Darfield 320
- Series8

**EXHIBIT 13: Section 4-4 Horizontal Displacement At Middle of Pier**



## SOIL-STRUCTURE INTERACTION

The wharf structure is founded on deep piles. For the purposes of estimating the soil reaction to lateral loads, generalized profiles were prepared allowing development of lateral soil-structure load-deflection “springs” (p-y springs). We developed the springs for timber piles to represent the interaction of the pile with soil. The computer software LPILE Plus 5.0 by Ensoft Inc. was used for the preparation of p-y springs based on published models of soil-structure interaction. The following parameters were used in our analyses.

**TABLE 6: Parameters Used in p-y Spring Development**


SOIL TYPE	SOIL MODEL	EFFECTIVE UNIT WEIGHT (PCF)	UNDRAINED STRENGTH – LINEAR INCREASE (PSF)	PHI (DEG)	K (PCI)	$\epsilon_{50}$
Fill	API Sand	60	-	38	Default	-
Young Bay Mud	Soft Clay (Matlock)	27.6	100 + 10/foot	-	-	Default
Old Bay Clay	Stiff Clay (no free water)	58.7	2000	-		Default
Alluvium	API Sand	60	0	40	Default	


Upper bound and lower bound of the springs were developed using the soil parameters above. The spring output was simplified by matching the curved shape with four points for ease of use by the marine structural engineer. The springs are attached in Appendix D.

The axial capacity of existing piles was also assessed. Springs that represent the load-deflection of the pile in both side friction (t-z) and end bearing (q-w) were developed using the computer software APILEPlus Version 5. Upper and lower bound estimates for the springs were developed. The springs are attached as Appendix E.

We are pleased to be of service on this project. If you have any questions or comments regarding this letter, please call and we will be glad to discuss them with you.

Sincerely,

  
Pedro Espinosa, GE



  
Jeff Fippin, GE



Attachments: Selected References  
Figures

Appendix A – Seed Ground Motions and Dynamic Properties  
Appendix B – Existing Condition Seismic Slope Stability at Section 8-8  
Appendix C – Analysis of DSM Buttress Section 6-6  
Appendix D – P-Y Springs  
Appendix E – Axial Capacities


## SELECTED REFERENCES

1. Anderson, et al., 2008, Seismic Analysis and Design of Retaining Walls, Buried Slopes, and Embankments, National Cooperative Highway Research Program (NCHRP) Report 611, Transportation Research Board, Washington, D.C., 137p.
2. Bray, J.D. and Travarasrou, T., 2007, Simplified Procedure for Estimation Earthquake Induced Deviatoric Slope Displacements, Journal of Geotechnical and Geoenvironmental Engineering, ACSE, V. 133 (4), pp. 381-392, April 2007.
3. California Geological Survey, 2008, Special Publication 117A, Guidelines for Evaluating and Mitigating Seismic Hazards in California.
4. ENGEO, 2012, Preliminary Geotechnical Report, Encinal Terminals, Alameda County, California, Project No. 9769.000.000, November 19, 2012.
5. ENGEO, 2017, Updated Geotechnical Report, Encinal Terminals, Alameda County, California, Project No. 9769.000.000, October 2, 2017.
6. Robertson, P. K. and R. G. Campanella, 1988, Guidelines for Geotechnical Design Using CPT and CPTU Data.
7. Spencer, E., 1967, A method of analysis of the stability of embankments assuming parallel inter-slice forces, Geotechnique, V. 17(1), pp. 11–26.
8. Stewart, J.P., Blake, T.F. and Hollingsworth, R.A., 2003, A Screen Analysis Procedure for Seismic Slope Stability, Earthquake Spectra, v.19, n.3, pp. 697-712.



## FIGURES

**Figure 1: Vicinity Map**  
**Figure 2: Site Plan**  
**Figure 3: Regional Geologic Map**  
**Figure 4: Regional Faulting and Seismicity**  
**Figures 5A-5B: Cross Sections**



0 1000 2000  
FEET  
0 1000 2000  
METERS



BASE MAP SOURCE: GOOGLE EARTH MAPING SERVICE



VICINITY MAP  
ENCINAL TERMINALS  
ALAMEDA, CALIFORNIA

PROJECT NO.: 9769.000.000

SCALE: AS SHOWN

DRAWN BY: GLJ

CHECKED BY: JAF

FIGURE NO.

1



C:\Working\DRAF-ING2\Draw\9769\000\GEA\0917\976900000-GEA-2-SitePlan-DeepSoilMapping-0917.dwg Plot Date: 10-02-17 g3rfe



#### EXPLANATION


ALL LOCATIONS ARE APPROXIMATE

- 4-CPT05 CONE PENETRATION TEST (ENGEO, JULY 2013)
- 3-CPT05 CONE PENETRATION TEST (ENGEO, JANUARY 2013)
- 2-CPT05 CONE PENETRATION TEST (ENGEO, NOVEMBER 2012)
- B1-6 BORING (ENGEO, JANUARY 2013)

--- HISTORIC SHORELINE (1885)

--- SITE BOUNDARY

8 8' CROSS SECTION LOCATION



BASE MAP SOURCE: GOOGLE EARTH MAPPING SERVICE



SITE PLAN  
ENCINAL TERMINALS  
ALAMEDA, CALIFORNIA

PROJECT NO.: 9769.000.000

SCALE: AS SHOWN

DRAWN BY: GLJ

CHECKED BY: JAF

FIGURE NO.

2

ORIGINAL FIGURE PRINTED IN COLOR





## EXPLANATION

af	Artificial fill (Historic)
Qhaf1	Younger alluvial fan deposits (Holocene)
Qds	Dune sand (Holocene and Pleistocene)
Qmt	Marine terrace deposits (Pleistocene)

BASE MAP SOURCE: GRAYMER, 2000



REGIONAL GEOLOGIC MAP  
ENCINAL TERMINALS  
ALAMEDA, CALIFORNIA

PROJECT NO.: 9769.000.000

SCALE: AS SHOWN

DRAWN BY: GLJ



CHECKED BY: JAF

FIGURE NO.

3



COPYRIGHT © 2017 BY ENGEO INCORPORATED. THIS DOCUMENT MAY NOT BE REPRODUCED IN WHOLE OR IN PART BY ANY MEANS WHATSOEVER, NOR MAY IT BE QUOTED OR EXCERPTED WITHOUT THE EXPRESS WRITTEN CONSENT OF ENGEO INCORPORATED.



EXPLANATION	
	MAGNITUDE 7+
	MAGNITUDE 6-7
	MAGNITUDE 5-6
	HISTORIC FAULT
	HOLOCENE FAULT
	QUATERNARY FAULT
	HISTORIC BLIND THRUST FAULT ZONE

BASE MAP SOURCE:  
U.S.G.S. 1-ARC SECOND S.R.T.M. DATABASE  
U.S.G.S. QUATERNARY FAULT DATABASE, MARCH, 2006  
U.S.G.S. HISTORIC EARTHQUAKE DATABASE (1800-2000)








REGIONAL FAULTING AND SEISMICITY  
ENCINAL TERMINALS  
ALAMEDA, CALIFORNIA

PROJECT NO.:	9769.000.000
SCALE:	AS SHOWN
DRAWN BY:	DLB
CHECKED BY:	JAF


FIGURE NO.  
**4**



SECTION 1-1' TO 4-4' ENGEOTERMINALS ALAMEDA, CALIFORNIA








EXPLANATION	
ALL LOCATIONS ARE APPROXIMATE	
FILL	ARTIFICIAL FILL
YBM	YOUNG BAY MUD (HOLOCENE)
CH + SC	INTERLAYERED ESTUARINE SANDS AND YOUNG BAY MUD (HOLOCENE)
OBD	OLD BAY DEPOSITS (PLEISTOCENE)
Qal	ALLUVIUM (PLEISTOCENE)
4-CPT05	CONE PENETRATION TEST (ENGEOTERMINALS, JULY 2013)
3-CPT05	CONE PENETRATION TEST (ENGEOTERMINALS, JANUARY 2013)
2-CPT05	CONE PENETRATION TEST (ENGEOTERMINALS, NOVEMBER 2012)
B1-6	BORING (ENGEOTERMINALS, JANUARY 2013)
SECTION 1-1' TO 4-4'	CROSS SECTION LINE





SECTION 5-5' 1"=50'




EXPLANATION OF BORING AND CPT SYMBOLS



EXPLANATION	
ALL LOCATIONS ARE APPROXIMATE	
FILL	ARTIFICIAL FILL
YBM	YOUNG BAY MUD (HOLOCENE)
CH + SC	INTERLAYERED ESTUARINE SANDS AND YOUNG BAY MUD (HOLOCENE)
OBD	OLD BAY DEPOSITS (PLEISTOCENE)
Qal	ALLUVIUM (PLEISTOCENE)
4-CPT05	CONE PENETRATION TEST (ENGE, JULY 2013)
3-CPT05	CONE PENETRATION TEST (ENGE, JANUARY 2013)
2-CPT05	CONE PENETRATION TEST (ENGE, NOVEMBER 2012)
B1-6	BORING (ENGE, JANUARY 2013)
SECTION 4	CROSS SECTION LINE

## APPENDIX A

### Seed Ground Motions and Dynamic Properties







Shear Wave Velocity Profile







Dynamic Properties





## RSN164 147



## RSN164 237







## RSN850 000













## RSN850 090







## RSN1495 E







## RSN1495 N







## RSN5780 EW







## RSN5780 NS



## RSN1004 270







## RSN1004 360













# RSN1602 000







## RSN1602 090



## RSN6911 N18E




## RSN6911 S72E



## APPENDIX B


### Existing Condition Seismic Slope Stability at Section 8-8





## **APPENDIX C**

### **Analysis of DSM Buttress Section 6-6**









## **APPENDIX D**

### **P-Y Springs**

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles  
STATION 5+10 & 10+00 Best Estimate

JOB NO. 9769.000.000  
MADE BY JAF  
DATE 10/2/17

p-y Curves								
Soil Type	Cumulative Depth Below Mudline at top of slope (ft)	Elevation (ft)	y1 (in)	p1 (psi)	y2 (in)	p2 (psi)	y3 (in)	p3 (psi)
Clay (YBM)	0	-7.7	1.1	20	5.9	35	7.7	38
	2	-9.7	0.5	25	5.9	59	7.7	63
	4	-11.7	0.5	36	5.9	85	7.7	91
	6	-13.7	0.5	49	5.9	115	7.7	123
	8	-15.7	0.5	63	5.9	147	7.7	158
	10	-17.7	2.8	144	5.9	183	7.7	196
	12	-19.7	2.8	175	5.9	222	7.7	238
	14	-21.7	2.8	200	5.9	254	7.7	272
	16	-23.7	2.8	216	5.9	275	7.7	295
	18	-25.7	2.8	233	5.9	296	7.7	318
Clay	20	-27.6	2.8	249	5.9	316	7.7	339
	20	-27.8	2.3	824	6.0	1,049	9.9	1,124
	22	-29.7	2.3	824	6.0	1,049	9.9	1,124
	24	-31.7	2.3	824	6.0	1,049	9.9	1,124
	26	-33.7	2.3	824	6.0	1,049	9.9	1,124
Sand	30	-37.7	0.3	3,771	0.7	7,025	0.9	7,025
	32	-39.7	0.1	3,194	0.7	8,894	0.9	8,894
	34	-41.7	0.1	3,982	0.7	10,982	0.9	10,982
	36	-43.7	0.1	4,876	0.7	13,289	0.9	13,289
	38	-45.7	0.1	5,886	0.7	15,814	0.9	15,814
Clay	40	-47.7	1.0	2,637	2.7	3,357	4.5	3,596
	42	-49.7	0.7	2,398	2.7	3,357	4.5	3,596
	44	-51.7	1.0	2,637	2.7	3,357	4.5	3,596
Clay	46	-53.7	0.3	26,788	0.5	40,300	0.8	51,397
	48	-55.7	0.2	25,960	0.7	54,531	0.9	54,531
	50	-57.7	0.2	27,708	0.7	57,666	0.9	57,666
	52	-59.7	0.2	29,466	0.7	60,800	0.9	60,800
	54	-61.7	0.2	32,120	0.7	63,935	0.9	63,935
Clay (Shell Layer)	56	-63.7	1.0	2,887	2.7	3,674	4.5	3,937

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles  
STATION 5+10 & 10+00 Lower Bound

JOB NO. 9769.000.000  
MADE BY JAF  
DATE 10/2/17

P multiplier 0.75

p-y Curves								
Soil Type	Cumulative Depth Below Mudline at top of slope (ft)	Elevation (ft)	y1 (in)	p1 (psi)	y2 (in)	p2 (psi)	y3 (in)	p3 (psi)
Clay (YBM)	0	-7.7	1.1	15	5.9	26	7.7	28
	2	-9.7	0.5	19	5.9	44	7.7	47
	4	-11.7	0.5	27	5.9	64	7.7	68
	6	-13.7	0.5	37	5.9	86	7.7	92
	8	-15.7	0.5	47	5.9	111	7.7	118
	10	-17.7	2.8	108	5.9	137	7.7	147
	12	-19.7	2.8	131	5.9	167	7.7	179
	14	-21.7	2.8	150	5.9	191	7.7	204
	16	-23.7	2.8	162	5.9	206	7.7	221
	18	-25.7	2.8	175	5.9	222	7.7	238
Clay	20	-27.6	2.8	186	5.9	237	7.7	254
	20	-27.8	2.3	618	6.0	787	9.9	843
	22	-29.7	2.3	618	6.0	787	9.9	843
	24	-31.7	2.3	618	6.0	787	9.9	843
	26	-33.7	2.3	618	6.0	787	9.9	843
Sand	30	-37.7	0.3	2,828	0.7	5,269	0.9	5,269
	32	-39.7	0.1	2,396	0.7	6,670	0.9	6,670
	34	-41.7	0.1	2,986	0.7	8,236	0.9	8,236
	36	-43.7	0.1	3,657	0.7	9,966	0.9	9,966
	38	-45.7	0.1	4,415	0.7	11,861	0.9	11,861
Clay	40	-47.7	1.0	1,978	2.7	2,517	4.5	2,697
	42	-49.7	0.7	1,798	2.7	2,517	4.5	2,697
	44	-51.7	1.0	1,978	2.7	2,517	4.5	2,697
Clay	46	-53.7	0.3	20,091	0.5	30,225	0.8	38,548
	48	-55.7	0.2	19,470	0.7	40,898	0.9	40,898
	50	-57.7	0.2	20,781	0.7	43,249	0.9	43,249
	52	-59.7	0.2	22,100	0.7	45,600	0.9	45,600
	54	-61.7	0.2	24,090	0.7	47,951	0.9	47,951
Clay (Shell Layer)	56	-63.7	1.0	2,165	2.7	2,756	4.5	2,952

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles  
STATION 5+10 & 10+00 Upper Bound

JOB NO. 9769.000.000  
MADE BY JAF  
DATE 10/2/17

P multiplier

1.5

p-y Curves								
Soil Type	Cumulative Depth Below Mudline at top of slope (ft)	Elevation (ft)	y1 (in)	p1 (psi)	y2 (in)	p2 (psi)	y3 (in)	p3 (psi)
Clay (YBM)	0	-7.7	1.1	15.1	5.9	26.5	7.7	28.4
	2	-9.7	0.5	18.8	5.9	43.9	7.7	47.1
	4	-11.7	0.5	27.3	5.9	63.8	7.7	68.3
	6	-13.7	0.5	36.8	5.9	86.0	7.7	92.1
	8	-15.7	0.5	47.4	5.9	110.5	7.7	118.4
	10	-17.7	2.8	108.0	5.9	137.4	7.7	147.2
	12	-19.7	2.8	131.0	5.9	166.7	7.7	178.6
	14	-21.7	2.8	149.7	5.9	190.5	7.7	204.1
	16	-23.7	2.8	162.2	5.9	206.4	7.7	221.1
	18	-25.7	2.8	174.6	5.9	222.3	7.7	238.1
	20	-27.6	2.8	186.5	5.9	237.3	7.7	254.3
Clay	20	-27.8	2.3	618.4	6.0	787.0	9.9	843.2
	22	-29.7	2.3	618.4	6.0	787.0	9.9	843.2
	24	-31.7	2.3	618.4	6.0	787.0	9.9	843.2
	26	-33.7	2.3	618.4	6.0	787.0	9.9	843.2
	30	-37.7	0.3	2828.2	0.7	5268.6	0.9	5268.6
Sand	32	-39.7	0.1	2395.9	0.7	6670.4	0.9	6670.4
	34	-41.7	0.1	2986.4	0.7	8236.4	0.9	8236.4
	36	-43.7	0.1	3656.8	0.7	9966.5	0.9	9966.5
	38	-45.7	0.1	4414.8	0.7	11860.7	0.9	11860.7
	40	-47.7	1.0	1978.0	2.7	2517.5	4.5	2697.3
Clay	42	-49.7	0.7	1798.2	2.7	2517.5	4.5	2697.3
	44	-51.7	1.0	1978.0	2.7	2517.5	4.5	2697.3
Clay	46	-53.7	0.3	20091.3	0.5	30224.8	0.8	38547.6
	48	-55.7	0.2	19469.8	0.7	40898.4	0.9	40898.4
	50	-57.7	0.2	20780.6	0.7	43249.2	0.9	43249.2
	52	-59.7	0.2	22099.8	0.7	45600.1	0.9	45600.1
	54	-61.7	0.2	24089.8	0.7	47950.9	0.9	47950.9
Clay (Shell Layer)	56	-63.7	1.0	2165.1	2.7	2755.6	4.5	2952.5

# Encinal Terminals - p-y Curves at Station 14+00

Section	Section 14+00						Nominal						
Material	Depth Below Mudline(feet)	p0 (psi)	y0 (in)	p1 (psi)	y1 (in)	p2 (psi)	y2 (in)	p3 (psi)	y3 (in)	p4 (psi)	y4 (in)	p5 (psi)	y5 (in)
Fill	0.5	0	0	24.0751	0.10678	37.45176	0.4875	42.93587	0.675	42.93587	0.81	42.93587	8
Fill	2.5	0	0	136.8909	0.10967	224.6803	0.4875	261.5603	0.675	261.5603	0.81	261.5603	8
Fill	4.9	0	0	216.6521	0.12162	404.9353	0.4875	490.6163	0.675	490.6163	0.81	490.6163	8
YBM	5.1	0	0	60.72	1.09227	83.49	2.83947	98.67	4.68693	106.26	5.85387	113.85	7.2
YBM	25	0	0	204	1.09227	280.5	2.83947	331.5	4.68693	357	5.85387	382.5	7.2
YBM	49.9	0	0	383.28	0.54613	527.01	1.41973	622.83	2.34347	670.74	2.92693	718.65	3.6
OBC	50.1	0	0	1050	0.17074	1500	0.71111	1800	1.47456	1950	2.031	2100	2.7318
OBC	55	0	0	1050	0.17074	1500	0.71111	1800	1.47456	1950	2.031	2250	3.6
OBC	60	0	0	1050	0.17074	1500	0.71111	1800	1.47456	1950	2.031	2250	3.6

Section	Section 14+00						Upper Bound						
Material	Depth Below Mudline(feet)	p0 (psi)	y0 (in)	p1 (psi)	y1 (in)	p2 (psi)	y2 (in)	p3 (psi)	y3 (in)	p4 (psi)	y4 (in)	p5 (psi)	y5 (in)
Fill	0.5	0	0	36.11265	0.10678	56.17764	0.4875	64.40381	0.675	64.40381	0.81	64.40381	8
Fill	2.5	0	0	205.3363	0.10967	337.0204	0.4875	392.3404	0.675	392.3404	0.81	392.3404	8
Fill	4.9	0	0	324.9782	0.12162	607.4029	0.4875	735.9245	0.675	735.9245	0.81	735.9245	8
YBM	5.1	0	0	91.08	1.09227	125.235	2.83947	148.005	4.68693	159.39	5.85387	170.775	7.2
YBM	25	0	0	306	1.09227	420.75	2.83947	497.25	4.68693	535.5	5.85387	573.75	7.2
YBM	49.9	0	0	574.92	0.54613	790.515	1.41973	934.245	2.34347	1006.11	2.92693	1077.975	3.6
OBC	50.1	0	0	1575	0.17074	2250	0.71111	2700	1.47456	2925	2.031	3150	2.7318
OBC	55	0	0	1575	0.17074	2250	0.71111	2700	1.47456	2925	2.031	3375	3.6
OBC	60	0	0	1575	0.17074	2250	0.71111	2700	1.47456	2925	2.031	3375	3.6

Section	Section						Lower Bound						
Material	Depth Below Mudline(feet)	p0 (psi)	y0 (in)	p1 (psi)	y1 (in)	p2 (psi)	y2 (in)	p3 (psi)	y3 (in)	p4 (psi)	y4 (in)	p5 (psi)	y5 (in)
Fill	0.5	0	0	18.05633	0.10678	28.08882	0.4875	32.2019	0.675	32.2019	0.81	32.2019	8
Fill	2.5	0	0	102.6682	0.10967	168.5102	0.4875	196.1702	0.675	196.1702	0.81	196.1702	8
Fill	4.9	0	0	162.4891	0.12162	303.7015	0.4875	367.9622	0.675	367.9622	0.81	367.9622	8
YBM	5.1	0	0	45.54	1.09227	62.6175	2.83947	74.0025	4.68693	79.695	5.85387	85.3875	7.2
YBM	25	0	0	153	1.09227	210.375	2.83947	248.625	4.68693	267.75	5.85387	286.875	7.2
YBM	49.9	0	0	287.46	0.54613	395.2575	1.41973	467.1225	2.34347	503.055	2.92693	538.9875	3.6
OBC	50.1	0	0	787.5	0.17074	1125	0.71111	1350	1.47456	1462.5	2.031	1575	2.7318
OBC	55	0	0	787.5	0.17074	1125	0.71111	1350	1.47456	1462.5	2.031	1687.5	3.6
OBC	60	0	0	787.5	0.17074	1125	0.71111	1350	1.47456	1462.5	2.031	1687.5	3.6



## **APPENDIX E**

### **Axial Capacities**

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 4/10/13

Best Estimate									
q-w Curves									
Station	Soil Type	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
1+10 to 10+00	Sand	Lower	45 to 55	-35 to -45	99.6	0.2	199.3	1.8	199.3
		Upper	45 to 55	-35 to -45	104.6	0.2	209.2	1.8	209.2
	Clay	Lower	55 to 65	-45 to -55	19.2	0.2	38.4	1.8	38.4
		Upper	55 to 65	-45 to -55	26.9	0.2	53.7	1.8	53.7
	Clay (Shell Layer)	--	65 to 85	-55 to -80	1.5	0.2	3.1	1.8	3.1
13+00	Clay (YBM)	Lower	50 to 60	-41 to -51	2.7	0.2	5.4	1.8	5.4
		Upper	50 to 60	-41 to -51	3.5	0.2	6.9	1.8	6.9
14+00	Clay (YBM)	Lower	44 to 54	-41 to -51	2.9	0.2	5.8	1.8	5.8
		Upper	44 to 54	-41 to -51	3.7	0.2	7.5	1.8	7.5
	Clay	Lower	54 to 59	-51 to -56	13.3	0.2	26.6	1.8	26.6
		Upper	54 to 59	-51 to -56	18.4	0.2	36.9	1.8	36.9

Upper Bound

p multiplier

1.5

q-w Curves									
Station	Soil Type	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
1+10 to 10+00	Sand	Lower	45 to 55	-35 to -45	149.4	0.4	299.0	2.7	299.0
		Upper	45 to 55	-35 to -45	156.9	0.4	313.8	2.7	313.8
	Clay	Lower	55 to 65	-45 to -55	28.8	0.4	57.5	2.7	57.5
		Upper	55 to 65	-45 to -55	40.3	0.4	80.6	2.7	80.6
	Clay (Shell Layer)	--	65 to 85	-55 to -80	2.3	0.4	4.6	2.7	4.6
13+00	Clay (YBM)	Lower	50 to 60	-41 to -51	4.0	0.4	8.1	2.7	8.1
		Upper	50 to 60	-41 to -51	5.2	0.4	10.4	2.7	10.4
14+00	Clay (YBM)	Lower	44 to 54	-41 to -51	4.4	0.4	8.7	2.7	8.7
		Upper	44 to 54	-41 to -51	5.6	0.4	11.2	2.7	11.2
	Clay	Lower	54 to 59	-51 to -56	20.0	0.4	39.9	2.7	39.9
		Upper	54 to 59	-51 to -56	27.6	0.4	55.3	2.7	55.3

Lower Bound

p multiplier

0.75

q-w Curves									
Station	Soil Type	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
1+10 to 10+00	Sand	Lower	45 to 55	-35 to -45	74.7	0.2	149.5	1.8	149.5
		Upper	45 to 55	-35 to -45	78.5	0.2	156.9	1.8	156.9
	Clay	Lower	55 to 65	-45 to -55	14.4	0.2	28.8	1.8	28.8
		Upper	55 to 65	-45 to -55	20.1	0.2	40.3	1.8	40.3
	Clay (Shell Layer)	--	65 to 85	-55 to -80	1.2	0.2	2.3	1.8	2.3
13+00	Clay (YBM)	Lower	50 to 60	-41 to -51	2.0	0.2	4.0	1.8	4.0
		Upper	50 to 60	-41 to -51	2.6	0.2	5.2	1.8	5.2
14+00	Clay (YBM)	Lower	44 to 54	-41 to -51	2.2	0.2	4.4	1.8	4.4
		Upper	44 to 54	-41 to -51	2.8	0.2	5.6	1.8	5.6
	Clay	Lower	54 to 59	-51 to -56	10.0	0.2	20.0	1.8	20.0
		Upper	54 to 59	-51 to -56	13.8	0.2	27.6	1.8	27.6

PROJECT Encinal Terminals  
SUBJECT C2 Timber Piles

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 10/2/17

q-w Curves									
Soil Type	Station	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
Clay	1+10	Lower	60 to 75	-70 to -85	115.7	0.2	231.4	1.9	231.4
	1+10	Upper	60 to 75	-70 to -85	118.3	0.2	236.7	1.9	236.7
	5+10	Lower	60 to 75	-70 to -85	111.5	0.2	223.0	1.9	223.0
	5+10	Upper	60 to 75	-70 to -85	114.1	0.2	228.3	1.9	228.3

Upper Bound

p multiplier

1.5

q-w Curves									
Soil Type	Station	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
Clay	1+10	Lower	60 to 75	-70 to -85	173.6	0.2	347.1	1.9	347.1
	1+10	Upper	60 to 75	-70 to -85	177.5	0.2	355.1	1.9	355.1
	5+10	Lower	60 to 75	-70 to -85	167.3	0.2	334.5	1.9	334.5
	5+10	Upper	60 to 75	-70 to -85	171.2	0.2	342.5	1.9	342.5

Lower Bound

p multiplier

0.75

q-w Curves									
Soil Type	Station	Upper/ Lower	Cumulativ e Depth Below Mudline (ft)	Elevation (ft)	q1 (kip)	w1 (in)	q2 (kip)	w2 (in)	q3 (kip)
Clay	1+10	Lower	60 to 75	-70 to -85	86.8	0.2	173.6	1.9	173.6
	1+10	Upper	60 to 75	-70 to -85	88.7	0.2	177.5	1.9	177.5
	5+10	Lower	60 to 75	-70 to -85	83.6	0.2	167.3	1.9	167.3
	5+10	Upper	60 to 75	-70 to -85	85.6	0.2	171.2	1.9	171.2

PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 1+10 Lower Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.4	0.2	0.4	0.4	0.4	3.6
	2	7.0	0.5	0.2	0.5	0.4	0.5	3.6
	4	5.0	0.6	0.2	0.6	0.4	0.6	3.6
	6	3.0	0.7	0.2	0.6	0.4	0.6	3.6
	8	1.0	0.8	0.2	0.8	0.4	0.8	3.6
	10	-1.0	2.0	0.2	1.8	0.4	1.8	3.6
Clay	12	-3.0	2.4	0.2	2.2	0.4	2.2	3.6
	14	-5.0	2.6	0.2	2.3	0.4	2.3	3.6
	16	-7.0	2.7	0.2	2.4	0.4	2.4	3.6
	18	-9.0	2.8	0.2	2.5	0.4	2.5	3.6
	20	-11.0	3.0	0.2	2.7	0.4	2.7	3.6
	22	-13.0	3.2	0.2	2.9	0.4	2.9	3.6
Sand	24	-15.0	4.0	0.2	3.6	0.4	3.6	3.6
	26	-17.0	5.1	0.1	6.4	0.1	6.4	2.0
	28	-19.0	5.6	0.1	7.0	0.1	7.0	2.0
	30	-21.0	6.1	0.1	7.7	0.1	7.7	2.0
	32	-23.0	6.7	0.1	8.3	0.1	8.3	2.0
	34	-25.0	7.2	0.1	9.0	0.1	9.0	2.0
	36	-27.0	7.7	0.1	9.7	0.1	9.7	2.0
	38	-29.0	8.3	0.1	10.3	0.1	10.3	2.0
Clay	40	-31.0	7.2	0.1	9.0	0.1	9.0	2.0
	42	-33.0	8.6	0.2	7.7	0.4	7.7	0.9
Sand	44	-35.0	9.8	0.2	8.8	0.4	8.8	3.6
	46	-37.0	11.0	0.1	13.7	0.1	13.7	2.0
	48	-39.0	11.5	0.1	14.4	0.1	14.4	2.0
	50	-41.0	13.1	0.1	14.6	0.1	14.6	2.0
	52	-43.0	11.7	0.1	14.6	0.1	14.6	2.0
	54	-45.0	11.7	0.1	14.6	0.1	14.6	2.0
Clay	56	-47.0	14.6	0.2	13.1	0.4	13.1	3.6

PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 1+10 Upper Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.5	0.2	0.4	0.4	0.4	3.6
	2	7.0	0.6	0.2	0.5	0.4	0.5	3.6
	4	5.0	0.7	0.2	0.6	0.4	0.6	3.6
	6	3.0	0.8	0.2	0.7	0.4	0.7	3.6
	8	1.0	0.9	0.2	0.8	0.4	0.8	3.6
Clay	10	-1.0	2.3	0.2	2.1	0.4	2.1	3.6
	12	-3.0	2.9	0.2	2.6	0.4	2.6	3.6
	14	-5.0	3.0	0.2	2.7	0.4	2.7	3.6
	16	-7.0	3.2	0.2	2.9	0.4	2.9	3.6
	18	-9.0	3.3	0.2	3.0	0.4	3.0	3.6
	20	-11.0	3.4	0.2	3.1	0.4	3.1	3.6
	22	-13.0	3.6	0.2	3.2	0.4	3.2	3.6
Sand	24	-15.0	4.4	0.2	4.0	0.4	4.0	3.6
	26	-17.0	5.5	0.1	6.8	0.1	6.8	2.0
	28	-19.0	6.0	0.1	7.5	0.1	7.5	2.0
	30	-21.0	6.6	0.1	8.3	0.1	8.3	2.0
	32	-23.0	7.2	0.1	9.0	0.1	9.0	2.0
	34	-25.0	7.7	0.1	9.7	0.1	9.7	2.0
	36	-27.0	8.3	0.1	10.4	0.1	10.4	2.0
	38	-29.0	8.9	0.1	11.1	0.1	11.1	2.0
Clay	40	-31.0	8.4	0.1	10.5	0.1	10.5	2.0
	42	-33.0	10.3	0.2	9.3	0.4	9.3	0.9
Sand	44	-35.0	11.5	0.2	10.4	0.4	10.4	3.6
	46	-37.0	12.2	0.1	15.2	0.1	15.2	2.0
	48	-39.0	12.8	0.1	16.0	0.1	16.0	2.0
	50	-41.0	14.6	0.1	16.2	0.1	16.2	2.0
	52	-43.0	13.0	0.1	16.2	0.1	16.2	2.0
Clay	54	-45.0	13.0	0.1	16.2	0.1	16.2	2.0
	56	-47.0	16.2	0.2	14.6	0.4	14.6	3.6

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles  
STATION 5+10 and 10+00 Lower Bound

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.4	0.2	0.4	0.4	0.4	3.6
	2	7.0	0.5	0.2	0.4	0.4	0.4	3.6
	4	5.0	0.6	0.2	0.5	0.4	0.5	3.6
	6	3.0	0.7	0.2	0.6	0.4	0.6	3.6
	8	1.0	0.8	0.2	0.8	0.4	0.8	3.6
	10	-1.0	1.0	0.2	0.9	0.4	0.9	3.6
	12	-3.0	1.1	0.2	1.0	0.4	1.0	3.6
	14	-5.0	1.2	0.2	1.1	0.4	1.1	3.6
	16	-7.0	1.3	0.2	1.2	0.4	1.2	3.6
	18	-9.0	1.4	0.2	1.3	0.4	1.3	3.6
Clay	20	-11.0	2.4	0.2	2.1	0.4	2.1	3.6
	22	-13.0	2.8	0.2	2.5	0.4	2.5	3.6
	24	-15.0	2.9	0.2	2.6	0.4	2.6	3.6
	26	-17.0	3.1	0.2	2.8	0.4	2.8	3.6
	28	-19.0	3.3	0.2	3.0	0.4	3.0	3.6
Sand	30	-21.0	5.5	0.2	4.9	0.4	4.9	3.6
	32	-23.0	5.4	0.1	6.7	0.1	6.7	2.0
	34	-25.0	5.9	0.1	7.4	0.1	7.4	2.0
	36	-27.0	6.4	0.1	8.1	0.1	8.1	2.0
	38	-29.0	7.0	0.1	8.7	0.1	8.7	2.0
Clay	40	-31.0	6.7	0.1	8.4	0.1	8.4	2.0
	42	-33.0	8.2	0.2	7.4	0.4	7.4	0.9
	44	-35.0	9.2	0.2	8.2	0.4	8.2	3.6
Clay	46	-37.0	9.6	0.1	10.8	0.1	12.0	2.0
	48	-39.0	10.1	0.1	12.7	0.1	12.7	2.0
	50	-41.0	12.1	0.1	13.4	0.1	13.4	2.0
	52	-43.0	11.3	0.1	14.1	0.1	14.1	2.0
	54	-45.0	10.7	0.1	13.4	0.1	13.4	2.0
Clay (Shell Layer)	56	-47.0	9.4	0.2	8.5	0.5	8.5	3.6

PROJECT Encinal Terminals  
SUBJECT C1 Timber Piles  
STATION 5+10 and 10+00 Upper Bound

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.5	0.2	0.4	0.4	0.4	3.6
	2	7.0	0.6	0.2	0.5	0.4	0.5	3.6
	4	5.0	0.7	0.2	0.6	0.4	0.6	3.6
	6	3.0	0.8	0.2	0.7	0.4	0.7	3.6
	8	1.0	0.9	0.2	0.8	0.4	0.8	3.6
	10	-1.0	1.0	0.2	0.9	0.4	0.9	3.6
	12	-3.0	1.1	0.2	1.0	0.4	1.0	3.6
	14	-5.0	1.2	0.2	1.1	0.4	1.1	3.6
	16	-7.0	1.4	0.2	1.2	0.4	1.2	3.6
	18	-9.0	1.5	0.2	1.3	0.4	1.3	3.6
Clay	20	-11.0	2.7	0.2	2.5	0.4	2.5	3.6
	22	-13.0	3.3	0.2	2.9	0.4	2.9	3.6
	24	-15.0	3.4	0.2	3.0	0.4	3.0	3.6
	26	-17.0	3.5	0.2	3.1	0.4	3.1	3.6
	28	-19.0	3.7	0.2	3.3	0.4	3.3	3.6
Sand	30	-21.0	5.9	0.2	5.3	0.4	5.3	3.6
	32	-23.0	5.8	0.1	7.2	0.1	7.2	2.0
	34	-25.0	6.4	0.1	8.0	0.1	8.0	2.0
	36	-27.0	6.9	0.1	8.7	0.1	8.7	2.0
	38	-29.0	7.5	0.1	9.4	0.1	9.4	2.0
Clay	40	-31.0	7.8	0.1	9.8	0.1	9.8	2.0
	42	-33.0	9.9	0.2	8.9	0.4	8.9	0.9
	44	-35.0	10.8	0.2	9.7	0.4	9.7	3.6
Sand	46	-37.0	10.7	0.1	13.3	0.1	13.3	2.0
	48	-39.0	11.3	0.1	14.1	0.1	14.1	2.0
	50	-41.0	13.4	0.1	14.9	0.1	14.9	2.0
	52	-43.0	12.6	0.1	15.7	0.1	15.7	2.0
	54	-45.0	12.1	0.1	15.2	0.1	15.2	2.0
Clay (Shell Layer)	56	-47.0	11.6	0.2	10.5	0.4	10.5	3.6

PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 13+00 Lower Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.0	0.2	0.0	0.4	0.0	3.6
	2	7.0	0.1	0.2	0.1	0.4	0.1	3.6
	4	5.0	0.2	0.2	0.2	0.4	0.2	3.6
	6	3.0	0.3	0.2	0.3	0.4	0.3	3.6
	8	1.0	0.4	0.2	0.4	0.4	0.4	3.6
	10	-1.0	0.5	0.2	0.5	0.4	0.5	3.6
	12	-3.0	0.6	0.2	0.5	0.4	0.5	3.6
	14	-5.0	0.7	0.2	0.6	0.4	0.6	3.6
	16	-7.0	0.8	0.2	0.7	0.4	0.7	3.6
	18	-9.0	0.9	0.2	0.8	0.4	0.8	3.6
	20	-11.0	1.0	0.2	0.9	0.4	0.9	3.6
	22	-13.0	1.1	0.2	1.0	0.4	1.0	3.6
	24	-15.0	1.2	0.2	1.1	0.4	1.1	3.6
	26	-17.0	1.3	0.2	1.2	0.4	1.2	3.6
	28	-19.0	1.4	0.2	1.2	0.4	1.2	3.6
	30	-21.0	1.5	0.2	1.3	0.4	1.3	3.6
	32	-23.0	1.6	0.2	1.4	0.4	1.4	3.6
	34	-25.0	1.7	0.2	1.5	0.4	1.5	3.6
	36	-27.0	1.8	0.2	1.6	0.4	1.6	3.6
	38	-29.0	1.9	0.2	1.7	0.4	1.7	3.6
	40	-31.0	2.0	0.2	1.8	0.4	1.8	3.6
	42	-33.0	2.1	0.2	1.9	0.4	1.9	0.9
	44	-35.0	2.2	0.2	1.9	0.4	1.9	3.6
	46	-37.0	2.3	0.2	2.0	0.4	2.0	3.6
	48	-39.0	2.4	0.2	2.1	0.4	2.1	3.6
	50	-41.0	2.4	0.2	2.1	0.4	2.1	3.6
	52	-43.0	2.4	0.2	2.1	0.4	2.1	3.6
	54	-45.0	2.4	0.2	2.1	0.4	2.1	3.6
	56	-47.0	2.4	0.2	2.1	0.4	2.1	3.6
	58	-49.0	2.4	0.2	2.1	0.4	2.1	3.6
	60	-51.0	2.4	0.2	2.1	0.4	2.1	3.6
Clay	62	-53.0	2.4	0.2	2.1	0.4	2.1	3.6
	64	-55.0	2.4	0.2	2.1	0.4	2.1	3.6
	66	-57.0	2.4	0.2	2.1	0.4	2.1	3.6

PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 13+00 Upper Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	9.0	0.1	0.2	0.1	0.4	0.1	3.6
	2	7.0	0.2	0.2	0.1	0.4	0.1	3.6
	4	5.0	0.3	0.2	0.2	0.4	0.2	3.6
	6	3.0	0.4	0.2	0.3	0.4	0.3	3.6
	8	1.0	0.5	0.2	0.4	0.4	0.4	3.6
	10	-1.0	0.6	0.2	0.6	0.4	0.6	3.6
	12	-3.0	0.7	0.2	0.7	0.4	0.7	3.6
	14	-5.0	0.8	0.2	0.8	0.4	0.8	3.6
	16	-7.0	1.0	0.2	0.9	0.4	0.9	3.6
	18	-9.0	1.1	0.2	1.0	0.4	1.0	3.6
	20	-11.0	1.2	0.2	1.1	0.4	1.1	3.6
	22	-13.0	1.3	0.2	1.2	0.4	1.2	3.6
	24	-15.0	1.4	0.2	1.3	0.4	1.3	3.6
	26	-17.0	1.5	0.2	1.4	0.4	1.4	3.6
	28	-19.0	1.6	0.2	1.5	0.4	1.5	3.6
	30	-21.0	1.8	0.2	1.6	0.4	1.6	3.6
	32	-23.0	1.9	0.2	1.7	0.4	1.7	3.6
	34	-25.0	2.0	0.2	1.8	0.4	1.8	3.6
	36	-27.0	2.1	0.2	1.9	0.4	1.9	3.6
	38	-29.0	2.2	0.2	2.0	0.4	2.0	3.6
	40	-31.0	2.3	0.2	2.1	0.4	2.1	3.6
	42	-33.0	2.4	0.2	2.2	0.4	2.2	0.9
	44	-35.0	2.6	0.2	2.3	0.4	2.3	3.6
	46	-37.0	2.7	0.2	2.4	0.4	2.4	3.6
	48	-39.0	2.8	0.2	2.5	0.4	2.5	3.6
	50	-41.0	2.8	0.2	2.5	0.4	2.5	3.6
	52	-43.0	2.8	0.2	2.5	0.4	2.5	3.6
	54	-45.0	2.8	0.2	2.5	0.4	2.5	3.6
	56	-47.0	2.8	0.2	2.5	0.4	2.5	3.6
	58	-49.0	2.8	0.2	2.5	0.4	2.5	3.6
	60	-51.0	2.8	0.2	2.5	0.4	2.5	3.6
Clay	62	-53.0	2.8	0.2	2.5	0.4	2.5	3.6
	64	-55.0	2.8	0.2	2.5	0.4	2.5	3.6
	66	-57.0	2.8	0.2	2.5	0.4	2.5	3.6



PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 14+00 Lower Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	3.0	0.0	0.2	0.0	0.4	0.0	3.6
	2	1.0	0.1	0.2	0.1	0.4	0.1	3.6
	4	-1.0	0.2	0.2	0.2	0.4	0.2	3.6
	6	-3.0	0.3	0.2	0.3	0.4	0.3	3.6
	8	-5.0	0.4	0.2	0.4	0.4	0.4	3.6
	10	-7.0	0.5	0.2	0.5	0.4	0.5	3.6
	12	-9.0	0.6	0.2	0.6	0.4	0.6	3.6
	14	-11.0	0.7	0.2	0.6	0.4	0.6	3.6
	16	-13.0	0.8	0.2	0.7	0.4	0.7	3.6
	18	-15.0	0.9	0.2	0.8	0.4	0.8	3.6
	20	-17.0	1.0	0.2	0.9	0.4	0.9	3.6
	22	-19.0	1.1	0.2	1.0	0.4	1.0	3.6
	24	-21.0	1.2	0.2	1.1	0.4	1.1	3.6
	26	-23.0	1.3	0.2	1.2	0.4	1.2	3.6
	28	-25.0	1.4	0.2	1.3	0.4	1.3	3.6
	30	-27.0	1.5	0.2	1.4	0.4	1.4	3.6
	32	-29.0	1.6	0.2	1.4	0.4	1.4	3.6
	34	-31.0	1.7	0.2	1.5	0.4	1.5	3.6
	36	-33.0	1.8	0.2	1.6	0.4	1.6	3.6
	38	-35.0	1.9	0.2	1.7	0.4	1.7	3.6
	40	-37.0	2.0	0.2	1.8	0.4	1.8	3.6
Clay	42	-39.0	2.1	0.2	1.9	0.4	1.9	0.9
	44	-41.0	2.2	0.2	2.0	0.4	2.0	3.6
	46	-43.0	2.3	0.2	2.1	0.4	2.1	3.6
	48	-45.0	2.4	0.2	2.2	0.4	2.2	3.6
	50	-47.0	2.4	0.2	2.2	0.4	2.2	3.6
	52	-49.0	2.4	0.2	2.2	0.4	2.2	3.6
	54	-51.0	2.4	0.2	2.2	0.4	2.2	3.6
	56	-53.0	2.4	0.2	2.2	0.4	2.2	3.6
	58	-55.0	2.4	0.2	2.2	0.4	2.2	3.6

PROJECT Encinal Terminals  
 SUBJECT C1 Timber Piles  
 STATION 14+00 Upper Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	t1 (psi)	z1 (in)	t2 (psi)	z2 (in)	t3 (psi)	z3 (in)
Clay (YBM)	0	3.0	0.1	0.2	0.1	0.4	0.1	3.6
	2	1.0	0.2	0.2	0.1	0.4	0.1	3.6
	4	-1.0	0.3	0.2	0.3	0.4	0.3	3.6
	6	-3.0	0.4	0.2	0.4	0.4	0.4	3.6
	8	-5.0	0.5	0.2	0.5	0.4	0.5	3.6
	10	-7.0	0.6	0.2	0.6	0.4	0.6	3.6
	12	-9.0	0.8	0.2	0.7	0.4	0.7	3.6
	14	-11.0	0.9	0.2	0.8	0.4	0.8	3.6
	16	-13.0	1.0	0.2	0.9	0.4	0.9	3.6
	18	-15.0	1.1	0.2	1.0	0.4	1.0	3.6
	20	-17.0	1.2	0.2	1.1	0.4	1.1	3.6
	22	-19.0	1.4	0.2	1.2	0.4	1.2	3.6
	24	-21.0	1.5	0.2	1.3	0.4	1.3	3.6
	26	-23.0	1.6	0.2	1.4	0.4	1.4	3.6
	28	-25.0	1.7	0.2	1.6	0.4	1.6	3.6
	30	-27.0	1.8	0.2	1.7	0.4	1.7	3.6
	32	-29.0	2.0	0.2	1.8	0.4	1.8	3.6
	34	-31.0	2.1	0.2	1.9	0.4	1.9	3.6
	36	-33.0	2.2	0.2	2.0	0.4	2.0	3.6
	38	-35.0	2.3	0.2	2.1	0.4	2.1	3.6
	40	-37.0	2.5	0.2	2.2	0.4	2.2	3.6
Clay	42	-39.0	2.6	0.2	2.3	0.4	2.3	0.9
	44	-41.0	2.7	0.2	2.4	0.4	2.4	3.6
	46	-43.0	2.8	0.2	2.5	0.4	2.5	3.6
	48	-45.0	2.9	0.2	2.6	0.4	2.6	3.6
	50	-47.0	3.0	0.2	2.7	0.4	2.7	3.6
	52	-49.0	3.0	0.2	2.7	0.4	2.7	3.6
	54	-51.0	3.0	0.2	2.7	0.4	2.7	3.6
	56	-53.0	3.0	0.2	2.7	0.4	2.7	3.6
	58	-55.0	3.0	0.2	2.7	0.4	2.7	3.6

PROJECT Encinal Terminals  
SUBJECT C2 Concrete Piles  
STATION 1+10 Lower Bound

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	T1 (psi)	Z1 (in)	T2 (psi)	Z2 (in)	T3 (psi)	Z3 (in)
Clay	0	-10.0	0.5	0.2	0.4	0.6	0.4	3.8
	2	-12.0	0.6	0.2	0.5	0.6	0.5	3.8
	4	-14.0	0.7	0.2	0.7	0.6	0.7	3.8
Sand	6	-16.0	1.1	0.1	1.3	0.1	1.3	2.0
	8	-18.0	1.6	0.1	2.0	0.1	2.0	2.0
	10	-20.0	2.1	0.1	2.6	0.1	2.6	2.0
	12	-22.0	2.5	0.1	3.2	0.1	3.2	2.0
	14	-24.0	3.0	0.1	3.8	0.1	3.8	2.0
	16	-26.0	3.5	0.1	4.0	0.1	4.4	2.0
	18	-28.0	4.0	0.1	4.5	0.1	5.0	2.0
	20	-30.0	5.4	0.1	6.0	0.1	6.7	2.0
Clay	22	-32.0	7.3	0.2	6.6	0.6	6.6	3.8
	24	-34.0	7.5	0.2	6.7	0.6	6.7	3.8
Sand	26	-36.0	6.4	0.1	8.0	0.1	8.0	2.0
	28	-38.0	6.9	0.1	8.7	0.1	8.7	2.0
	30	-40.0	7.5	0.1	9.4	0.1	9.4	2.0
	32	-42.0	8.1	0.1	9.1	0.1	10.1	2.0
	34	-44.0	8.1	0.1	9.1	0.1	10.1	2.0
Clay	36	-46.0	8.4	0.2	7.6	0.4	7.6	3.8
	38	-48.0	8.5	0.2	7.6	0.4	7.6	3.8
	40	-50.0	8.6	0.2	7.7	0.4	7.7	3.8
	42	-52.0	8.7	0.2	7.9	0.4	7.9	0.9
Clay (Shell Layer)	44	-54.0	7.0	0.2	6.3	0.4	6.3	3.8
	46	-56.0	1.4	0.2	1.3	0.4	1.3	3.8
	48	-58.0	1.4	0.2	1.3	0.4	1.3	3.8
	50	-60.0	1.4	0.2	1.3	0.4	1.3	3.8
	52	-62.0	1.4	0.2	1.3	0.4	1.3	3.8
	54	-64.0	1.4	0.2	1.3	0.4	1.3	3.8
	56	-66.0	1.4	0.2	1.3	0.4	1.3	3.8
Clay	58	-68.0	1.4	0.2	1.3	0.4	1.3	3.8
	60	-70.0	8.6	0.2	7.8	0.4	7.8	3.8
	62	-72.0	11.2	0.2	10.1	0.4	10.1	3.8
	64	-74.0	11.4	0.2	10.2	0.4	10.2	3.8
	66	-76.0	11.6	0.2	10.4	0.4	10.4	3.8
	68	-78.0	11.7	0.2	10.6	0.4	10.6	3.8
	70	-80.0	11.9	0.2	10.7	0.4	10.7	3.8
	72	-82.0	12.1	0.2	10.9	0.6	10.9	3.8
	74	-84.0	12.1	0.2	10.9	0.6	10.9	3.8

PROJECT Encinal Terminals  
SUBJECT C2 Concrete Piles  
STATION 1+10 Upper Bound

JOB NO. 9769.000.000  
MADE BY SOS  
DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	T1 (psi)	Z1 (in)	T2 (psi)	Z2 (in)	T3 (psi)	Z3 (in)
Clay	0	-10.0	0.5	0.2	0.4	0.4	0.4	3.8
	2	-12.0	0.6	0.2	0.5	0.4	0.5	3.8
	4	-14.0	0.8	0.2	0.7	0.4	0.7	3.8
Sand	6	-16.0	1.2	0.1	1.4	0.1	1.4	2.0
	8	-18.0	1.7	0.1	2.1	0.1	2.1	2.0
	10	-20.0	2.2	0.1	2.8	0.1	2.8	2.0
	12	-22.0	2.7	0.1	3.4	0.1	3.4	2.0
	14	-24.0	3.3	0.1	4.1	0.1	4.1	2.0
	16	-26.0	3.8	0.1	4.7	0.1	4.7	2.0
	18	-28.0	4.3	0.1	5.4	0.1	5.4	2.0
	20	-30.0	6.3	0.1	7.9	0.1	7.9	2.0
Clay	22	-32.0	8.8	0.2	7.9	0.4	7.9	3.8
	24	-34.0	8.9	0.2	8.0	0.4	8.0	3.8
Sand	26	-36.0	7.1	0.1	8.9	0.1	8.9	2.0
	28	-38.0	7.7	0.1	9.7	0.1	9.7	2.0
	30	-40.0	8.4	0.1	10.5	0.1	10.5	2.0
	32	-42.0	9.0	0.1	11.2	0.1	11.2	2.0
	34	-44.0	9.3	0.1	11.6	0.1	11.6	2.0
Clay	36	-46.0	10.8	0.2	9.7	0.4	9.7	3.8
	38	-48.0	10.9	0.2	9.8	0.4	9.8	3.8
	40	-50.0	11.1	0.2	10.0	0.4	10.0	3.8
	42	-52.0	11.2	0.2	10.1	0.4	10.1	0.9
Clay (Shell Layer)	44	-54.0	8.8	0.2	7.9	0.4	7.9	3.8
	46	-56.0	1.4	0.2	1.3	0.4	1.3	3.8
	48	-58.0	1.4	0.2	1.3	0.4	1.3	3.8
	50	-60.0	1.4	0.2	1.3	0.4	1.3	3.8
	52	-62.0	1.4	0.2	1.3	0.4	1.3	3.8
	54	-64.0	1.4	0.2	1.3	0.4	1.3	3.8
	56	-66.0	1.4	0.2	1.3	0.4	1.3	3.8
Clay	58	-68.0	1.4	0.2	1.3	0.4	1.3	3.8
	60	-70.0	10.3	0.2	9.3	0.4	9.3	3.8
	62	-72.0	13.4	0.2	12.1	0.4	12.1	3.8
	64	-74.0	13.5	0.2	12.2	0.4	12.2	3.8
	66	-76.0	13.6	0.2	12.3	0.4	12.3	3.8
	68	-78.0	13.7	0.2	12.4	0.4	12.4	3.8
	70	-80.0	13.8	0.2	12.4	0.4	12.4	3.8
	72	-82.0	14.0	0.2	12.6	0.4	12.6	3.8
	74	-84.0	14.0	0.2	12.6	0.4	12.6	3.8

PROJECT Encinal Terminals  
 SUBJECT C2 Concrete Piles  
 STATION 5+10 Lower Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	T1 (psi)	Z1 (in)	T2 (psi)	Z2 (in)	T3 (psi)	Z3 (in)
Clay	0	-10.0	0.5	0.2	0.4	0.4	0.4	3.8
	2	-12.0	0.6	0.2	0.5	0.4	0.5	3.8
	4	-14.0	0.6	0.2	0.6	0.4	0.6	3.8
	6	-16.0	0.7	0.2	0.6	0.4	0.6	3.8
	8	-18.0	0.8	0.2	0.7	0.4	0.7	3.8
Sand	10	-20.0	1.6	0.2	1.5	0.4	1.5	3.8
	12	-22.0	1.9	0.1	2.4	0.1	2.4	2.0
	14	-24.0	2.4	0.1	3.0	0.1	3.0	2.0
	16	-26.0	2.9	0.1	3.6	0.1	3.6	2.0
	18	-28.0	3.4	0.1	4.2	0.1	4.2	2.0
Clay	20	-30.0	5.1	0.1	6.3	0.1	6.3	2.0
	22	-32.0	7.1	0.2	6.4	0.4	6.4	3.8
Sand	24	-34.0	7.1	0.2	6.4	0.4	6.4	3.8
	26	-36.0	5.7	0.1	7.1	0.1	7.1	2.0
	28	-38.0	6.2	0.1	7.8	0.1	7.8	2.0
	30	-40.0	6.8	0.1	8.5	0.1	8.5	2.0
	32	-42.0	7.4	0.1	9.2	0.1	9.2	2.0
Clay	34	-44.0	7.5	0.1	9.4	0.1	9.4	2.0
	36	-46.0	8.2	0.2	7.4	0.4	7.4	3.8
	38	-48.0	8.3	0.2	7.5	0.4	7.5	3.8
	40	-50.0	8.5	0.2	7.6	0.4	7.6	3.8
	42	-52.0	8.6	0.2	7.7	0.4	7.7	0.9
Clay (Shell Layer)	44	-54.0	6.8	0.2	6.1	0.4	6.1	3.8
	46	-56.0	1.4	0.2	1.3	0.4	1.3	3.8
	48	-58.0	1.4	0.2	1.3	0.4	1.3	3.8
	50	-60.0	1.4	0.2	1.3	0.4	1.3	3.8
	52	-62.0	1.4	0.2	1.3	0.4	1.3	3.8
	54	-64.0	1.4	0.2	1.3	0.4	1.3	3.8
	56	-66.0	1.4	0.2	1.3	0.4	1.3	3.8
Clay	58	-68.0	1.4	0.2	1.3	0.4	1.3	3.8
	60	-70.0	8.4	0.2	7.6	0.4	7.6	3.8
	62	-72.0	10.9	0.2	9.8	0.4	9.8	3.8
	64	-74.0	11.1	0.2	10.0	0.4	10.0	3.8
	66	-76.0	11.3	0.2	10.2	0.4	10.2	3.8
	68	-78.0	11.5	0.2	10.3	0.4	10.3	3.8
	70	-80.0	11.7	0.2	10.5	0.4	10.5	3.8
	72	-82.0	11.8	0.2	10.7	0.4	10.7	3.8
	74	-84.0	11.9	0.2	10.7	0.4	10.7	3.8

PROJECT Encinal Terminals  
 SUBJECT C2 Concrete Piles  
 STATION 5+10 Upper Bound

JOB NO. 9769.000.000  
 MADE BY SOS  
 DATE 10/2/17

t-z Curves								
Soil Type	Cumulative Depth Below Mudline (ft)	Elevation (ft)	T1 (psi)	Z1 (in)	T2 (psi)	Z2 (in)	T3 (psi)	Z3 (in)
Clay	0	-10.0	0.5	0.2	0.4	0.4	0.4	3.8
	2	-12.0	0.6	0.2	0.5	0.4	0.5	3.8
	4	-14.0	0.6	0.2	0.6	0.4	0.6	3.8
	6	-16.0	0.7	0.2	0.6	0.4	0.6	3.8
	8	-18.0	0.8	0.2	0.7	0.4	0.7	3.8
Sand	10	-20.0	1.7	0.2	1.5	0.4	1.5	3.8
	12	-22.0	2.0	0.1	2.6	0.1	2.6	2.0
	14	-24.0	2.6	0.1	3.2	0.1	3.2	2.0
	16	-26.0	3.1	0.1	3.9	0.1	3.9	2.0
	18	-28.0	3.6	0.1	4.5	0.1	4.5	2.0
Clay	20	-30.0	6.0	0.1	7.5	0.1	7.5	2.0
	22	-32.0	8.5	0.2	7.7	0.4	7.7	3.8
	24	-34.0	8.4	0.2	7.6	0.4	7.6	3.8
	26	-36.0	6.3	0.1	7.9	0.1	7.9	2.0
	28	-38.0	7.0	0.1	8.7	0.1	8.7	2.0
Sand	30	-40.0	7.6	0.1	9.5	0.1	9.5	2.0
	32	-42.0	8.2	0.1	10.3	0.1	10.3	2.0
	34	-44.0	8.7	0.1	10.8	0.1	10.8	2.0
	36	-46.0	10.6	0.2	9.5	0.4	9.5	3.8
	38	-48.0	10.7	0.2	9.7	0.4	9.7	3.8
Clay	40	-50.0	10.9	0.2	9.8	0.4	9.8	3.8
	42	-52.0	11.0	0.2	9.9	0.4	9.9	0.9
	44	-54.0	8.7	0.2	7.8	0.4	7.8	3.8
	46	-56.0	1.4	0.2	1.3	0.4	1.3	3.8
	48	-58.0	1.4	0.2	1.3	0.4	1.3	3.8
Clay (Shell Layer)	50	-60.0	1.4	0.2	1.3	0.4	1.3	3.8
	52	-62.0	1.4	0.2	1.3	0.4	1.3	3.8
	54	-64.0	1.4	0.2	1.3	0.4	1.3	3.8
	56	-66.0	1.4	0.2	1.3	0.4	1.3	3.8
	58	-68.0	1.4	0.2	1.3	0.4	1.3	3.8
Clay	60	-70.0	10.2	0.2	9.2	0.4	9.2	3.8
	62	-72.0	13.2	0.2	11.9	0.4	11.9	3.8
	64	-74.0	13.4	0.2	12.0	0.4	12.0	3.8
	66	-76.0	13.5	0.2	12.1	0.4	12.1	3.8
	68	-78.0	13.6	0.2	12.2	0.4	12.2	3.8
	70	-80.0	13.7	0.2	12.3	0.4	12.3	3.8
	72	-82.0	13.8	0.2	12.4	0.4	12.4	3.8
	74	-84.0	13.8	0.2	12.4	0.4	12.4	3.8